## KADUR DIVISION.

ADVERTISEMENT.

*The 4th June* 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 25th June 1891, for opening the new right bank Channel to the Keresante Tank, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 to 5.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for opening the new right bank Channel to the Kerasante Tank, Kadur Taluk," in default of which, tenders will be rejected.

5 The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Opening the new right bank Channel to the Keresante Tank, Kadur Taluk.

| Items of Work. | Per. | Rate. | Quantity. |
|---|---|---|---|
| *Anekat*, 200 *feet long.* | | | |
| Benching rock | C. Ft. | | 1,052 |
| Excavating foundation soft rock mixed with earth | C. Yd. | | 36 |
| Burnt brick in surki mortar | C. Ft. | | 1,354 |
| Rough stone (hearting) of good quality with mortar | C. Yd. | | 55 |
| Burnt stone slabs set in mortar | S. ft. | | 945 |
| Surki mortar plastering | Sq. | | 18·60 |
| Do pointing | Sq. | | 10·00 |
| Rough stone work, dry | C. Yd. | | 240 |
| Teak wood shutter for scouring sluice | C. Ft. | | 4 |
| Earthwork watering and tamping | C. Yd. | | 3,600 |
| *Head Sluice*, 2 *Vents* 3′ × 4′. | | | |
| Excavating foundation soft rock | C. Yd. | | 83 |
| Burnt brick in surki mortar | C. ft. | | 1,714 |
| Burnt stone slabs set in mortar | S. Ft. | | 255 |
| Surki mortar plastering | Sq. | | 13·26 |
| Teak wood shutters | C. ft. | | 11 |
| Rough stone work, dry | C. Yd. | | 84 |
| *Channel.* | | | |
| Excavating soft rock and gravel mixed with stone boulders | C. Yd. | | 5,500 |
| Ordinary soil excavating | C. Yd. | | 10,890 |
| Relieving weirs, ordinary design | Ft. | | 80 |
| Madabayi sluices | Each. | | 8 |
| Cattle bridges | Do | | 4 |
| Index stones | Do | | 69 |
| Grade stones | Do | | 73 |

A. GOVINDACHARLU,
*Executive Engineer.*

## CARRIAGE NOTICE.

THE BAND-CUBBON PARK.

*The 2nd June* 1891.

Parking of the carriages will be carried out by the Police.

Carriages should enter the space (opposite the Public Offices) reserved for parking, by the *Cantonment* on north side of the Park, and leave by the *Pettah* on south side.

Owners of carriages are requested to instruct their coachmen accordingly.

J. W. KNIGHT,
*Supt. of Police, Bangalore District.*